


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Harper County, Sec. 36 Twp. 32S Rge. (E) 6 (W)

Location as "NE/CNW&SW" or footage from lines NW NW NE  
Lease Owner Dorset Co.  
Lease Name Robinson Well No. 1  
Office Address 610 National Bank of Tulsa Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-20-61 19  
Application for plugging filed 6-19-61 19  
Application for plugging approved 6-19-61 19  
Plugging commenced 6-19-61 19  
Plugging completed 6-20-61 19  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4855 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud 4855' to 240'  
Cement 240' - 190'  
Mud 190' - 35'  
Cement 35' - 0'

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1961

CONSERVATION DIVISION  
Wichita, Kansas

00-28-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor V. W. McKnab  
Address Box 808, Winfield, Kansas

STATE OF Kansas, COUNTY OF Cowley, ss.

V. W. McKnab (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. W. McKnab

Box 808, Winfield, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 61

Michaels  
Notary Public.

My commission expires Aug. 21, 1961

INVOICED

DATE 6/29/61

INV. NO. 3352-W

WELL RECORD  
 Robinson #1  
 NW NW NE Sec. 36-32S-6W  
 Harper County, Kansas

Operator: Derset Co.  
 Contractor: V. W. McKnab

Date Comm: 6-2-61  
 Date Under Surf: 6-3-61  
 Date Comp: 6-20-61

DRILLER'S LOG:

0 - 287	Soil & Shale
287 - 987	Shale & Shells
987 - 2862	Lime & Shale
2862 - 2920	Sand
2920 - 3055	Sand & Shale
3055 - 3152	Shale & Lime
3152 - 3190	Sand
3190 - 3268	Shale
3268 - 3505	Lime & Shale
3505 - 3573	Sand
3573 - 3726	Lime & Shale
3726 - 4008	Lime
4008 - 4176	Lime & Shale
4176 - 4236	Lime
4236 - 4350	Lime & Shale
4350 - 4384	Lime
4384	Miss. Lime
4384 - 4445	Lime
4445 - 4478	Grey Lime
4478 - 4790	Lime
4790 - 4838	Lime & Shale
4838 - 4855	Simpson Sand
4855	T.D.

Cement and Casing Record:

12 Jts. 8 5/8" casing cemented at 252'  
 with 200 sks. HA 500

Plugging Record:

Mud	4855' to 240'
Cement	240' to 190'
Mud	190' to 35'
Cement	35' to Surface

Job completed 2:00 a.m. 6-20-61

ACKNOWLEDGED:

V. W. McKnab

BY *V. W. McKnab*

June 24, 1961

Subscribed and sworn to before me this 24th day of June, 1961.

*Melvin L. Lusk*  
 Notary Public

My Commission expires Aug. 21, 1961

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 28 1961

CONSERVATION DIVISION  
 Wichita, Kansas

06-28-1961