

15-077-30108-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:

Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 31 Twp 32S Rge 6W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NW NW  
Lease Owner National Cooperative Refinery Association  
Lease Name Prouse Well No. 1  
Office Address Box 6, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-11-66 19  
Application for plugging filed 7-11-66 19  
Application for plugging approved 7-11-66 19  
Plugging commenced 7-11-66 19  
Plugging completed 7-11-66 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4873 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	271.90'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 260, set plug with 1/4 sk. hulls and 25 sks. cement  
Mudded to 40, set plug with 1/4 sk. hulls and 10 sks. cement  
Added 2 sks. cement in rathole

STATE CORPORATION COMMISSION

JUL 10 1966

CONSERVATION DIVISION  
Wichita, Kansas

07-15-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1966

My commission expires April 1, 1967 Ulanda Nichols Notary Public.

15-077-30108-00-00

DRILLER'S LOG

COMPANY: National Cooperative Refinery Association  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: PROUSE #1  
 LOCATION: C NW NW SEC. 31-32S-6W HARPER COUNTY, KANSAS  
 COMMENCED: 6-27-66  
 COMPLETED: 7-11-66

0	271	Redbed, Shale
271	1350	Shale, Shells
1350	1850	Lime, Shale
1850	2245	Shale, Lime
2245	2400	Shale
2400	2600	Shale, Lime
2600	2965	Lime, Shale
2965	3140	Lime, Shale, Sandy
3140	3280	Shale
3280	3480	Shale, Lime Streaks
3480	3577	Lime, Shale
3577	3690	Sand
3690	3800	Shale, Sand
3800	3910	Shale, Lime
3910	4363	Lime
4363	4440	Lime, Shale
4440	4454	Mississippi
4454	4510	Lime, Chert
4510	4576	Lime
4576	4696	Lime, Chert
4696	4706	Shale
4706	4729	Chert, Lime
4729	4789	Lime, Shale
4789	4841	Shale, Lime
4841	4858	Shale
4858	4861	Sand
4861	4873	Sand, Shale
	<u>4873</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 15 1966  
 07-15-1966  
 CONSERVATION DIVISION  
 TOPEKA, KANSAS

Set 8 5/8" new 24# surface casing @ 271.90' with 200 sacks Common with 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Prouse #1 well, located C NW NW of Section 31, Township 32 South, Range 6 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 14th day of July, 1966.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires: April 1, 1967