

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-077-00201-00-00

WELL PLUGGING RECORD

Harper County, Sec. 22 Twp. 32S Rge. (E) 7 (W)

Location as "NE/CNW&SW" or footage from lines C NE NE NE  
Lease Owner Cooperative Refinery Association  
Lease Name Weigle "B" Well No. 1  
Office Address Box 765 Gt/ Bend, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed November 15 19 58  
Application for plugging filed November 15 19 58  
Application for plugging approved Verbal permission obtained 19  
Plugging commenced November 15 19 58  
Plugging completed November 15 19 58  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, verbal

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4795 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	271	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 140', dumped 1/2 s x. hulls, set plug, dumped 20 sx. cement, filled with heavy mud to 40', 1/2 s x. hulls, bridge plug, filled with 10 sx. cement to top.

*Free rd*  
11-20-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drlg. Company  
Address Russell, Ks.

STATE OF KANSAS COUNTY OF BARTON, ss.  
John H. Nation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation  
Box 765 Gt. Bend, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 19 day of November, 19 58

My commission expires Sept. 24, 1960

Yvonne Adams Notary Public.

PLUGGING  
FILE SEC. 22 T 32 R 7W  
BOOK PAGE 146 LINE 33

DRILLERS LOG

Weigle "B" #1

Elevation: 1407 G.L.  
Casing: 8 5/8 @ 271' w/ 225 sx.

Loc: C NE NE NE  
Sec: 22-32S-7W  
Harper County, Kansas  
Operator: Cooperative Refinery Ass'n.  
Contractor: Shields Drlg. Company

Comm: 10-28-58 Comp: 11-15-58  
R.T.D. 4795'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	120	Surface soil, sand strk <del>s</del> , redbed
120	235	Redbed
235	280	Cement
280	1050	Redbed, shale and salt
1050	1380	Shale with lime streaks
1380	1900	Lime with shale
1900	3643	Lime and shale
3643	3848	Sand and shale
3848	3905	Lime with shale
3905	4089	Lime
4089	4396	Lime and shale
4396	4442	Lime and chert
4442	4487	Lime
4487	4527	Lime and chert
4527	4561	Lime
4561	4631	Lime and chert
4631	4650	Lime
4650	4778	Lime and shale
4778	4793	Shale, lime, sand
4793	4795	Sand
4795		R.T.D.

(STATE OF KANSAS )  
(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Weigle "B" #1 well, located C NE NE NE of Section 22-32S-7W, Harper County, Kansas.

John H. Nation

Subscribed and sworn to before me this 19 day of November 1958.

Yvonne Adams

My commission expires: September 24, 1960.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 22 T. 32 R. 7W  
BOOK PAGE 146 LINE 33