


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above
Section Plat

Harper County, Sec. 21 Twp. 32S Rge. 7 (50) (W)
Location as "NE/CNW&SW&" or footage from lines SW SW SW
Lease Owner Sierra Petroleum Co., Inc.
Lease Name KLINGESMITH Well No. 1
Office Address 420 W. Douglas Ave., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 10/11/56 1956
Application for plugging filed 10/26/56 1956
Application for plugging approved 10/29/56 1956
Plugging commenced 10/29/56 1956
Plugging completed 11/7/56 1956
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Oct 26 1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	226	none
				5 1/2	4552	3443

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock to 4370', dumped 5 sax cement @ 4370' with dump bailer. Top of cement, 4335'. Pumped in 36 sax of Gel-Mud @ 2000' by Globe Cem. Co. Filled with mud to 220', set rock bridge, dumped 20 sax cement. Top of cement 160'. Filled hole with mud to 35', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address Box 711, Great Bend, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
S. P. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 56

My commission expires 1-30-57

Margie Cooper
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1956

CONSERVATION DIVISION
Wichita, Kansas

11-13-1956

PLUGGING
FILE SEC 21 T. 32 R. 7W
BOOK PAGE 110 LINE 45

15-077-00036-00-01

SIERRA PETROLEUM CO., INC.

KLINGLESMTIH #1 (Opened up old hole)

SW SW SW Sec. 21-22-7N
Harper County, Kansas

Total Depth: 4630

Comm: 10/5/56
Comp: 10/11/56

Casing:

8 5/8" @ 226'
5 1/2" @ 4552

Cement

165 sacks of Comm
150 sks Bulk Cement

FORMATION	DEPTH
Sand - Redbed & Shale	226
Redbed & Shale	530
Shale & Shells	945
Salt	1035
Shale & Shells	1155
Anhydrite	1180
Shale & Shells	1510
Shale & Lime	3310
Shale, Lime & Sand	3380
Shale & Lime	3860
Lime	4070
Lime & Shale	4385
Lime	4405
Lime & Chert	4552
Lime	4630

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

E. P. [Signature]

Subscribed and sworn to before me this 15th day of October, 1956.

Margie Cooper
Notary Public

My commission expires: 1-30-57.

PLUGGING
FILE SEC. 21, T. 32, R. 7W
BOOK PAGE 110, LINE 45

RECEIVED
NOTARY COMMISSION
NOV 13 1956
SERVATION DIVISION
Wichita, Kansas

11-13-1956