


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec. 18 Twp. 32S Rge. 7 (E) (W)
Location as "NE/CNW/SW" or footage from lines Center of NE SW
Lease Owner Mill Drilling Company, Inc.
Lease Name Zuercher Well No. 1
Office Address Pratt, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-31-65 19
Plugging completed 3-13-65 19
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 1660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	225	None
				5 1/2	None	3310

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rigging up. Blowing gas.
Cleaned out cellar.
Sanded hole from 1660' to 1320'. Build 10' rock bridge. Dumped 5 sacks of cement at 1365'.
Shot pipe at 3600' - 3500' - 3400' & 3300'. Pulling pipe.
Pulling pipe.
Build 10' rock bridge at 210'. Dumped 25 sacks of cement. Mudded to 110' rock bridge. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1965

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

03-17-1965
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of March 1965

My commission expires May 27, 1965

Notary Public.

15-077-00104-00-00

COPY


MULL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- MULL DRILLING CO. ET AL
Famr- Zuercher No. 1

SEC. 18 T. 32 R. 7W
C NE SW

Total Depth. 4855'
Comm. 7-15-59 Comp. 8-1-59
Shot or Treated.
Contractor. Mull Drilg. Co.
Issued. 12-31-60

County Harper
KANSAS



Elevation. 1417' RB

Production. 3,750,000 CFG

Meas. from top of RB. Figures indicate Bottom of Formations.

red bed	700
shale w/shells	1250
lime & shale	1710
lime	1840
lime & shale	2821
sandy lime & shale	3450
lime & shale	3931
lime	4383
lime w/shale	4408
Mississippi	4691
shale & lime	4728
Kinderhook shale	4778
Viola	4787
Viola chert & lime	4808
Simpson	4855
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1965
01-18-1965
CONSERVATION DIVISION
Wichita, Kansas

TOPS: SCOUT	
Heebner	3276
Douglas	3400
Douglas Sand	3612
Stalnaker	3698
Kansas City	3865
Mississippi	4408
Kinderhook	4691
Viola	4778
Simpson	4839