


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above
Section Plat

Harper County. Sec. 17 Twp. 32S Rge. 7W (XXXXXXXXXX)
Location as "NE/CNW&SW&" or footage from lines C SE SE
Lease Owner Walters Drilling Co.
Lease Name Baker 'C' Well No. 1
Office Address 510 Orpheum Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-12-65 19
Application for plugging filed 8-12-65 19
Application for plugging approved 8-12-65 19
Plugging commenced 8-12-65 19
Plugging completed 8-12-65 19
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4787 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 200' w/ mud
Set bottom plug @ 200' w/ 25 sx.
Set top plug @ 40' w/ 10 sx.
2 sx cement - rathole

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1965

CONSERVATION DIVISION
Wichita, Kansas

08-18-1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.
Address 510 Orpheum Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters (owner & operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X

510 Orpheum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1965

My commission expires October 4, 1967

Juanita M. Green
Notary Public.

DRILLER'S LOG

COMPANY: WALTERS DRILLING CO.
 510 ORPHEUM BUILDING
 WICHITA, KANSAS 67202

WELL NAME: BAKER 'C' #1
 LOCATION: C SE SE SEC. 17-32S-7W
 HARPER COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
 510 ORPHEUM BUILDING
 WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED: AUGUST 1, 1965
 ROTARY DRILLING COMPLETED: AUGUST 12, 1965

ELEVATION: 1408 KB

CASING RECORD: 8 5/8" @ 211' w/ 175 sks.

LOG

0 - 10	Sand
10 - 212	Red Rock and Shale
212 - 490	Shale
490 - 1310	Shale and Shells
1310 - 1555	Shale and Lime
1555 - 2365	Lime and Shale
2365 - 2735	Shale and Lime
2735 - 2920	Shale and Lime Streaks
2920 - 3030	Lime and Shale
3030 - 3435	Shale and Lime
3435 - 3590	Sandy Shale and Lime
3590 - 3710	Shale and Lime
3710 - 3845	Lime and Shale
3845 - 4025	Lime
4025 - 4160	Lime and Shale
4160 - 4235	Lime
4235 - 4335	Lime and Shale
4335 - 4421	Lime and Shale Miss. Chat
4421 - 4535	Lime and Chert
4535 - 4635	Chert and Lime
4635 - 4700	Shale
4700 - 4746	Shale and Lime
4746 - 4775	Lime
4775 - 4787	Sand
<u>4787</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 18 1965
 08-18-1965
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY Robert F. Walters
 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
 this 17th day of August, 1965.

Juanita M. Green
 Juanita M. Green, Notary Public

My Commission Expires: October 4, 1967