


15-077-01032-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

HARPER County, Sec. 16 Twp. 32s Rge. (E) 7 (W)
Location as "NE/CNW&SW&W" or footage from lines. C NW NW
Lease Owner PETROLEUM, INC.
Lease Name MUIR Well No. 2
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed OCTOBER 14 1960
Application for plugging filed JANUARY 31 1961
Application for plugging approved FEBRUARY 2 1961
Plugging commenced FEBRUARY 2 1961
Plugging completed FEBRUARY 7 1961
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED W. HAMPEL

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4760 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
VIOLA	WATER & LITTLE OIL	4718'	4722'	8-5/8"	218'	NONE
				5-1/2"	4756'	4160'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK T.D. 4760'

FILLED HOLE WITH CRUSHED ROCK FROM 4760' TO 4700', PLACED 4 SACKS CEMENT ON TOP CRUSHED ROCK. MUDDED UP WITH HEAVY MUD TO 210' AND BUILT SOLID ROCK BRIDGE, PLACED 20 SACKS CEMENT ON TO ROCK BRIDGE. MUDDED UP WITH HEAVY MUD TO 40' AND BUILT SOLID ROCK BRIDGE, PLACED 10 SACKS CEMENT ON TO ROCK BRIDGE TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1961

CONSERVATION DIVISION
Wichita, Kansas

02-17-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE
Address 102 WEST 18TH STREET, HUTCHINSON, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of FEBRUARY, 19 61

Arthur J. Miles
Notary Public.

My commission expires APRIL 14, 1963



WELL LOG

15-077-01032-00-00

COMPANY PETROLEUM, INCORPORATED

SEC. 16 T-32S R. 7W

FARM MUIR NO. 2

LOC. C-NW, NW


TOTAL DEPTH 4760'

COUNTY HARPER CO., KANSAS

COMM. Septgember 7, 1960 COMP. September 21, 1960

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8 5/8" @ 218' w/150 sax.
5 1/2" @ 4756' w/125 sax.



ELEVATION 1420' DF

PRODUCTION Dry & Abandoned

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Clay & shale
80	Sand & shale
218	Red bed & shale
475	Red bed
1160	Shale & shells
1260	Lime
2240	Lime & shale
3880	Shale & lime
4038	Lime
4140	Lime & shale
4270	Lime
4390	Lime & shale
4412	Lime & chert
4415	Lime
4443	Lime & chert
4604	Chert
4612	Shale & lime
4712	Shale
4760	Lime & shale
4760	T. D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1961

CONSERVATION DIVISION
Wichita, Kansas

02-07-1961

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #2 MUIR well

Verne A. Morris

Subscribed and sworn to before me this 4th day of October 19 60

My Commission Expires: April 14, 1963

Arthur J. Mule
NOTARY PUBLIC