


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Harper County, Sec. 14 Twp. 32S Rge. 7 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NW
Lease Owner Morrison Drilling Company, Inc.
Lease Name Sanders Well No. 1
Office Address Drawer 712, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 16 19 53
Application for plugging filed Verbal December 16 19 53
Application for plugging approved Verbal December 16 19 53
Plugging commenced December 16 19 53
Plugging completed December 16 19 53
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4767' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned pits. Raised mud weight. Half way out of hole circulated 30 min.
Set bridge at bottom of surface and spotted w/15 sax cement thru 6 jts. drill pipe.
Filled with rotary mud to 20' of surface and capped with 5 sax cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Morrison Drilling Company, Inc.
Address Drawer 712, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
C. W. Wilson (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
Drawer 712, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of December, 19 53

Am. Biles
Notary Public.

My commission expires January 10, 1955.

24-7368-5 3-53-20M
PLUGGING
FILE SEC 14 T 32 R 2W
BOOK PAGE 2 LINE 25

12-19-1953

WELL LOG - Sanders #1

OPERATOR: Morrison Drilling Company, Inc.
 Drawer 712
 El Dorado, Kansas

LOCATION: SE SE NW
 Section 14-32S-7W
 Harper County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
 Drawer 712
 El Dorado, Kansas

PRODUCTION: D & A

Farm: Leo Sanders Well No. 1

Date Commenced: November 28, 1953
 Date Completed: December 16, 1953

Total Depth: 4767 feet - Rotary

<u>From</u>	<u>To</u>	<u>Formation</u>
0	200	Cement
200	435	Red Bed
435	705	Shale & Shells
705	730	Red Bed
730	1250	Shale & Shells
1250	1510	Shale & Lime
1510	1580	Anhydrite, lime
1580	1830	Lime & Shale
1830	1915	Lime
1915	1935	Lime & Shale
1935	2185	Shale & Lime strks.
2185	2370	Shale & Lime
2370	2505	Shale & Lime strks.
2505	2690	Lime & Shale
2690	2780	Lime
2780	3110	Lime & Shale
3110	3180	Shale & Lime strks.
3180	3290	Lime & Shale
3290	3390	Shale & Lime strks.
3390	3591	Shale
3591	3598	Lime
3598	3654	Sand - Stalnaker
3654	3750	Sandy Shale & Lime
3750	3808	Shale
3808	4030	Lime
4030	4118	Lime & Shale
4118	4336	Lime
4336	4385	Lime & Shale
4385	4400	Lime
4400	4423	Chat
4423	4649	Lime
4649	4756	Shale
4756	4757	Lime
4757	4767	Snad
4767		Total Depth.

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Sanders #1 well drilled for Morrison Drilling Company, Inc., and completed December 16, 1953.

PLUGGING
 FILE SEC 14 T 32 R 7W
 BOOK PAGE 2 LINE 25

MORRISON DRILLING COMPANY, INC.

C. W. Wilson
 C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
) ss.
 COUNTY OF BUTLER)

12-19-1953

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public in and for the County and State aforesaid this 18th day of December, 1953.

My Commission Expires January 10, 1955.

Notary Public
 Notary Public