

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-21,134-0000

LEASE NAME Corley

WELL NUMBER 1-19

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 19 TWP. 27 RGE. 18 (S or W)

COUNTY Kiowa

Date Well Completed 5-11-85

Plugging Commenced 5-12-85

Plugging Completed 5-12-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Bogert Oil Company

ADDRESS 2601 NW Expressway-#901-W, Oklahoma City, Okl.

PHONE# (405) 848-5808 OPERATORS LICENSE NO. 5349

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5010

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	<u>319</u>	8 5/8"	5-4-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plugged well with 135 sxs 60/40 poz, 3% cc, 2% gel as follows: 1230'-50 sxs; 600'-50 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs; mousehole-10 sxs; water well-5 sxs. Job by Sun Cementing. Plug down at 8:45 a.m. on May 12, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124


STATE OF Kansas COUNTY OF Pratt, ss. CONSERVATION DIVISION
 Wichita, Kansas

Arnie Little

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 85

Mary L. Tjaden
 Notary Public

My Commission Expires: 3/22/88



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Corley #1-19
 C SE NW Sec. 19-27S-18W
 Kiowa County, Kansas
 Commenced: 5-3-85
 Completed: 5-12-85
 API #15-097-21,134
 Operator: Bogert Oil Company


Depth		Formation	Remarks
From	To		
0	200	Sand	Ran 12 joints (506') new, 23#, 8 5/8" surface casing. Set at 519' with 125 sxs Lite, 3% cc and 100 sxs Common, 2% gel, 3% cc. Cement did circulate. Job by Sun Cementing. Plug down at 1:15 p.m. on May 4, 1985.
200	380	Blue Shale	
380	490	Sand	
490	529	Blue Shale	
529	1640	Red Bed	
1640	2190	Red Bed, Shale	
2190	5010	Lime, Shale T.D.	RTD 5010'
			Plugged well with 135 sxs 60/40 poz, 3% cc, 2% gel as follows: 1230'-50 sxs; 600'-50 sxs; 40'-10 sxs with solid bridge; rathole-10 sxs; mousehole-10 sxs; water well-5 sxs. Job by Sun Cementing. Plug down at 8:45 a.m. on May 12, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
 ARNIE LITTLE, VICE-PRESIDENT



Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED
 STATE CORPORATION COMMISSION

JUN 04 1985

CONSERVATION DIVISION
 Wichita, Kansas