

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 19 Twp. 16S Rge. (E) 26(W)

Location as "NE/CNW%SW%" or footage from lines NW SE NE

Lease Owner Thunderbird Drilling, Inc.

Lease Name McBee "A" Well No. 1

Office Address 4328 East Kellogg, P. O. Box 18407, Wichita, Kansas 67218

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 12 1972

Application for plugging filed March 12 1972

Application for plugging approved March 12 1972


Plugging commenced March 12 1972

Plugging completed March 12 1972

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4567 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	338.43'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 800' with 70 sacks of regular cement; plugged at 300' with 20 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 11:30 A. M. March 12, 1972.



(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling, Inc.

Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)



Subscribed and sworn to before me this 13th day of March, 1972

Elaine H. Taylor
Notary Public

D R I L L E R S L O G

15135-20581-0000

#1 McBee "A"

CASING RECORD:
332.40' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NW SE NE
Section 19-16S-26W
Ness County, Kansas

TOTAL DEPTH:
4567'

COMMENCED: February 28, 1972
COMPLETED: March 12, 1972

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Shale & Sand	0	367	Ran 332.40' of used 8-5/8" surface casing; set and cemented at 338.43' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 9:00 P. M. February 28, 1972.
Shale & Clay	367	691	
Shale, Clay w/ Sand Streaks	691	1461	
Shale & Shells	1461	1472	
Anhydrite	1472	1500	
Red Bed & Shale	1500	1571	
Dakota Sand	1571	1829	
Red Bed & Shale	1829	2020	
Shale	2020	2076	
#2 Anhydrite	2076	2109	
Shale	2109	2273	
Shale & Shells	2273	2537	
Shale, Lime w/Broken Lime	2537	2667	
Lime & Shale	2667	3017	
Shale, Lime w/Broken Lime	3017	3205	
Shale & Lime	3205	3917	
Lime	3917	4536	
Chert	4536	4559	
Lime	4559	4563	
Chert, Lime & Shale	4563	4567	

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1972
CONSERVATION DIVISION
Wichita, Kansas

Rotary Total Depth 4567'

D. & A.

Plugged hole as follows: Plugged at 800' with 70 sacks of regular cement; plugged at 300' with 20 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 11:30 A. M. March 12, 1972.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 13th day of March, 1972.

My Commission Expires:

December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public

