

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County, Sec. 17 Twp. 15S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE 1/4 SW 1/4 SW 1/4

Lease Owner Birmingham-Bartlett Drilling Co.

Lease Name Anschutz 'B' Well No. 1

Office Address 300 Kaufman Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed _____ 19__

Application for plugging filed (verbally approved) July 2, 1965

Application for plugging approved (verbally approved) _____ 19__


Plugging commenced June 30, 1965

Plugging completed June 30, 1965

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2967 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	276'	8-5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 270'.
1/4 sack hulls and 25 sacks cement mixed and poured through drill pipe
10 sacks cement & 1/2 sack hulls on top plug set at 40'
3 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address (given above)

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Richard Hindery, partner of Birmingham-Bartlett Drilling Co. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery Partner
300 Kaufman Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1965

My commission expires November 29, 1966.

Vivian F. Yinger
Vivian F. Yinger, Notary Public.

ANSCHUTZ 'B' NO. 1 WELL

LOCATION: SE $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$ Sec. 17-15S-12W
Russell County, Kansas

SPUDDED: 6-25-65

COMPLETED: 6-30-65

OWNER, OPERATOR
and CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita, Kansas

SURFACE CASING: 8-5/8" O.D. 20# 8 rd. Thd. casing
set at 276' with 185 sacks cement.

OIL STRING: None set. Dry Hole.
Plugged: 6-30-65

LOG

(Figures indicate bottom of formation)

0 - 277	Clay, Shale & Sand
520	Shale & Shells
796	Sand & Redbed
826	Anhydrite
1075	Shale & Shells
2040	Shale & Lime
2270	Shale & Shells
2515	Shale
2769	Lime & Shale
2878	Lime
2967	Lime & Shale
2967	Rotary Total Depth

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the Anschutz 'B' No. 1 Well, as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By

Richard Hindery
Richard Hindery, Partner

Subscribed and sworn to before
me this 2nd day of July, 1965.

Vivian F. Yinger
Vivian F. Yinger, Notary Public

My commission expires November 29, 1966.

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1965
CONSERVATION DIVISION
Wichita, Kansas