

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-009-57739-00-00

LEASE NAME Frees/Burmeister

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3630 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Zinszer Oil Company, Inc.

SEC. 3 TWP. 17 RGE. 11 (X) or (W)

ADDRESS P.O. Box 211, Hays, Kansas 67601

COUNTY Rush

PHONE (785) 625-9448 OPERATORS LICENSE NO. 6239

Date Well Completed 9/18/40

Character of Well Oil

Plugging Commenced 6/18/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/19/01

The plugging proposal was approved on 6/18/01 (date)

by Herb Dienes, witnessed by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? no if not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3323 Bottom 3331 T.O. 3331

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle.	Oil	3324	0	4 1/2	3324	none.
3324 - 3331		340	0	7	340	none

RECEIVED  
MAR 2002

Describe in detail the manner in which the well was plugged, indicating where and fluid was placed and the method or methods used in introducing it into the hole. If cement plug were used, state the character of same and depth placed, from feet to feet each set  
6/18/01 drilled cement from 315 to 348, drilled cement from 442 to 520, drilled red shale to 722, drilled anhydrite to 730. 6/19/10 run tbg to 700, pumped 50 sx 60/40 pozmix 10% gel, cement circ. to surface, pull tbg out, pumped down 4 1/2 csq 50sx 60/40 pozmix 10% gel with 200# hulls, max 375 psi, SIP 250 psi, pumped .1 bbl cement into 8 5/8" pressure to 300 psi.

Name of Plugging Contractor Swift Services License No. 32382

Address Ness City, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinszer Oil Company, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman

(Employee of Operator) ~~XXXXXXXXXXXX~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 211, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 28<sup>th</sup> day of February, 2002.

[Signature]  
Notary Public

My Commission Expires: August 24, 2002



OR

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


DERBY OIL CO.  
Free No. 3.

SEC. 3 T. 17 R. 11W  
CN 1/2 SW NE

Total Depth. 3331'  
Comm. 9-18-40 Comp. 10-14-40  
Shot or Treated. 1000 Gals. Acid  
Contractor. Crow Drilg. Co.  
Issued. 12-14-40

Rotary 3326  
Cable 3331

County. Barton



CASING:  
7" 340'  
4 1/2" 3324'

Elevation. 1918'

Production Depth. Pot. 6580 B.

Figures Indicate Bottom of Formations.

shale & shells	328
shale	340
shale & shells	515
red bed	640
shale & shells	722
anhydrite	742
shale	864
shale & shells	1185
shale & salt	1385
shale & limo	1916
lime	1970
shale & lime	2017
shale	2120
shale & limo	2226
shale	2386
shale & lime	2710
shale	2720
lime	2753
shale & lime	2776
lime	2801
shale & lime	2831
lime	2944
shale & lime	3011
shale	3052
lime	3163
lime sft	3169
lime	3288
shale & lime	3323
dolomite	3331-1413
Total Depth.	

No. 1 & 13 same  
No. 2 & 14 same

No. 1 & 2 Free  
in Card File  
Old Card

3067-72

3086-70

3153-68

3229-71

Cable tools:  
D.P. & D.D. to 3326  
1050' oil 1 hr  
1435' oil 1 hr, 30 min  
D.D. to 3328  
2180' oil 2 hr, 30 min  
D.D. to 3330  
3015' oil 6 hrs  
D.D. to 3331 T.D.  
3060' oil 7 1/2 hrs  
Swabbed 46 BOPH 3 hrs off btn  
1000 acid thru tubing  
Swabbed 67 BOPH 2 hrs  
1200' off btn

Tops: Lansing 3052 (wh line) 1134  
Arbuckle 3323 - 1405  
good porosity & saturation

Note: All measurements derrick floor

KANSAS CORPORATION COMMISSION

MAY 24 2001

CONSERVATION DIVISION