

STATE OF KANSAS
STATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,557-00-00

LEASE NAME KNOP "C"

WELL NUMBER 2

2310 Ft. from ^N Section Line

2310 Ft. from ^W Section Line

SEC. 2 TWP. 20S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 11-12-01

Plugging Completed 11-13-10

RECEIVED

NOV 19 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR EAGLE PETROLEUM, INC.

ADDRESS P.O. Box 106 Bushton, Kansas 67427

PHONE# (620) 793-2037 OPERATORS LICENSE NO. 3309

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on _____ (date)

Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	261'	None
				5-1/2"	3345'	1990'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3290' and 5 sacks cement. Shot pipe @2421', 2011' and 1990'. Pulled pipe up to 1425', pumped 100 sks. cement with 300# hulls, pulled up to 625', pumped 40 sks. cement, pulled up to 250' and circulated 85 sks. cement, 60/40 pos. 10% gel. Layed down rest of casing. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eagle Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

do hereby depose and swear that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 16th day of November 2001

My Commission Expires: _____

