

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-21,396-00-00

LEASE NAME McCurry

WELL NUMBER 5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970 Ft. from ^N Section Line

330 Ft. from ^W Section Line

SEC. 36 TWP. 17S RGE. 14W (E) or (W)

COUNTY Barton

LEASE OPERATOR L.D. DRILLING, INC.

ADDRESS R.R. #1 Box 183B Great Bend, Kansas 67530

PHONE#(620) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil

Date Well Completed _____

Plugging Commenced 5-1-01

Plugging Completed 5-3-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	803'	None
				4-1/2"	3400'	1800'

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 2001
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3150' and 4 sks. cement. Shot pipe @2400', 2200', 2000' and 1800', pulled up to 1550', pumped 75 sks. cement w/300# hulls, pulled up to 850', pumped 40 sks. cement w/100# hulls, pulled up to 250' and circulated 70 sks. cement to surface. 60/40 pos, 10% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of May 2001

[Signature]
Notary Public

My Commission Expires: _____

