

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 115 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-009-21, 196-00-00

LEASE NAME Woodburn

WELL NUMBER 1

990 Ft. from <sup>N</sup> Section Line

1650 Ft. from <sup>W</sup> Section Line

SEC. 34 TWP. 20S RGE. 14W (E) or  (W)

RECEIVED  
 DEC 10 2002  
 KCC WICHITA

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 W. 22nd. St. North, Bldg. 300 Wichita, Ks. 67226

COUNTY Barton

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 12-2-02

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-3-02

The plugging proposal was approved on \_\_\_\_\_ (date)

Patrick Staab (KCC District Agent's Name).

ACO-1 filled? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3568'

show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	828'	None
				5-1/2"	3567'	2020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from feet to feet each sack. Plugged off bottom with sand to 3360' and 5 sacks cement. Shot pipe @2010', pulled up to 1625', pumped 115 sacks cement and 300# hulls, pulled up to 875', pumped 40 sacks cement and 200# hulls, pulled up to 400' and circulated 60 sacks cement to surface. 60/40 pos, 10% gel Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of December, 2002

[Signature]  
 Notary Public

My Commission Expires:

