

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130-S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-009-19021-00-00
 API NUMBER Drilled 2-2-46

LEASE NAME Conner

WELL NUMBER 3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 21 TWP. 17S RGE. 14W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 5-15-01

Plugging Completed 5-16-01

LEASE OPERATOR RUSSELL OIL, INC.

ADDRESS 3535 N.W. 58th St., Suite 1060 Okla. City, OK. 73112

PHONE# (405) 947-9900 OPERATORS LICENSE NO. 3293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3363'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED
KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	837'	None
				5-1/2"	3355'	None

Describe in detail the manner in which the well was plugged, indicating where the mud plugs placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s
Plugged off bottom with sand to 2300' and 5 sks. cement. Shot pipe @2000', pipe parted. Shot pipe @1560' and 760'. Ran 2" tubing to 1550', pumped 110 sks. cement and 400# bulls, pulled up to 750' and circulated 160 sks. cement. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of May, 2001

[Signature]
 Notary Public

My Commission Expires: _____



OR