

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-009-07390-00-00  
API NUMBER Comp. 2-15-56

LEASE NAME Spacil

WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 28 TWP. 20S RGE. 12W (E) or (W)

COUNTY Barton

LEASE OPERATOR ZENITH DRILLING CORPORATION

ADDRESS P.O. Box 780428 Wichita, Kansas 67278-0428

PHONE# (316) 684-9777 OPERATORS LICENSE NO. 5141

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-9-01

Plugging Completed 5-11-01

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3437'

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS | CASING RECORD | KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	253'	None
				4-1/2"	3424'	None

MAY 23 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl...  
Ran 1500' of tubing, perforated well @1325' and 625', pumped 125 sks. cement w/600# hulls and circulated to surface. Pulled tubing, hooked onto 4-1/2" casing and pumped 175 sks. cement. Pressured to 500#, shut-in 400#. Hooked ont annulas, pumped 10 sks. cement, 60/40 pos. 10% gel. Pressured up to 500#, shut-in 400#.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zenith Drilling Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of May, 2001

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CP  
Revised 05-

OK