

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-07392-00-00
API NUMBER Comp. 1-21-57

LEASE NAME Spacil

WELL NUMBER _____

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 28 TWP. 20S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 5-9-01

Plugging Completed 5-10-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ZENITH DRILLING CORPORATION

ADDRESS P.O. Box 780428 Wichita, Kansas 67278-0428

PHONE#(316) 684-9777 OPERATORS LICENSE NO. 5141

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3442'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	253'	None
				4-1/2"	3415'	None

MAY 23 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Plugged off bottom with sand to 3350' and 4 sks. cement. Ran 1200' of tubing, perforated well @1200' and 600', pumped 210 sks. cement w/500# hulls, didn't circulate, pumped 185 sks. cement w/200# hulls and circulated to surface. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zenith Drilling Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances stated herein, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 2001

[Signature]
Notary Public

My Commission Expires: _____



Form CR
Revised 05-

OR