

API NUMBER 15- 077-21,177-00-00

LEASE NAME Morgan

WELL NUMBER 3-1

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 3 TWP. 33 RGE. 5 (R) or (W)

COUNTY Harper

Date Well Completed: 7-21-88

Plugging Commenced 7-22-88

Plugging Completed 7-22-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR William H. Davis

ADDRESS 1520 Liberty Tower, Oklahoma City, OK 73102

PHONE# (405) 236-4029 OPERATORS LICENSE NO. 4511

Character of Well Dry D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 19, 1988 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Will be by Operator If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom 3500' T.D.

Show depth and thickness of all water, oil and gas \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION  
 CASING RECORD

OIL, GAS OR WATER RECORDS

Formation	Content	From	To	Put In	Pulled out
				<u>JUL 29 1988</u>	<u>07-29-1988</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

1st plug set @ 900' w/35 sacks

2nd plug set @ 388' w/35 sacks

3rd plug set at 60' w/25 sacks

10 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Company, Inc. License No. 5929

Address 620 Hubbard, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

John Armbruster

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John J. Armbruster

(Address) 620 Hubbard, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28 day of July, 19 88

Dorothy M. Hague  
 Notary Public



DRILLERS' WELL LOG

15-077-21177-00-00  
Morgan #3-1?

DATE COMMENCED: July 16, 1988

DATE COMPLETED: July 22, 1988

William H. Davis  
MORGAN #1  
SE NE NE  
Sec. 3-Twp.33,R5W  
Harper County, KS

0 - 538' Surface Soil, Sand, Shale  
338 - 1634' Shale & Lime  
1634 - 2262' Lime, Shale  
2262 - 3166' Lime  
3166 - 3356' Shale, Sand  
3356 - 3500' Shale, Lime  
- 3500 RTD

Elevation: 1314 K.B.

Surface Pipe:  
Set 8 5/8" 24# at 338'  
w/200 sacks 60/40 Pozmix,  
2% gel, 3% C.C.

A F F I D A V I T


STATE OF KANSAS  
COUNTY OF BARTON) ss

JOHN ARMBRUSTER of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*John Armbruster*  
John Armbruster

SUBSCRIBED AND SWORN to before me this 28 day of July, 1988.

*Dorothy M. Hague*  
Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
07-29-1988  
JUL 29 1988

CONSERVATION DIVISION  
Wichita, Kansas