

15-077-20143-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Harper County, Sec. 22 Twp. 33S Rge. (E) 5W (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner Landes Exploration Company

Lease Name Southern Well No. 1

Office Address Box 867, Magnolia, Arkansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-31 1972

Application for plugging filed 3-31 1972

Application for plugging approved 3-31 1972

Plugging commenced 3-31 1972

Plugging completed 3-31 1972

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4908 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	208'	8-5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fluid to 180', 1/2 sx hulls, plug, 25 sx cement;
Fluid to 40', 1/2 sx hulls, plug, 10 sx cement;
Two Sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas
04-04-1972

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor D N B DRILLING, INC.

Address 737 First Nat'l Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF ss. JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
737 First Nat'l Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of April, 1972



Ella Priess Notary Public.

15-077-20143-00-00

DRILLERS' LOG

LANDES EXPLORATION COMPANY
No. 1 Southern
C SE SE, Sec. 22-33S-5W
Harper County, Kansas

Elev: 1280 R.B.

Commenced: 3-21-72
Completed: 3-31-72

Surface: 200' of 8-5/8"
cemented w/175 sx cement, 38 cc.
3-22-72

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 208
Shale	208 - 870
Shale & Lime	870 - 1814
Lime & Shale	1814 - 2080
Shale & Lime	2080 - 2339
Lime & Shale	2339 - 3230
Lime, Shale & Sand	3230 - 3482
Shale & Lime	3482 - 3704
Lime	3704 - 4060
Lime & Shale	4060 - 4182
Shale & Lime	4182 - 4419
Lime	4419 - 4720
Lime & Shale	4720 - 4747
Shale & Lime	4747 - 4874
Lime & Shale	4874 - 4879
Sand	4879 - 4908 T.D.

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas
04-04-1972

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 3rd day of April, 1972.

My Commission Expires:
August 25, 1972

Ella Priess
Ella Priess, Notary Public

