

15-135-22376-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ness SEC. 25 TWP. 16 RGE. 26 SE/NW
 Location as in quarters or footage from lines:
 SE NW SW

Lease Owner Raymond Oil Co., Inc.
 Lease Name Bondurant Well No. #1
 Office Address Suite 900, One Main Place Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 3-26-83
 Application for plugging filed 3-26-83
 Plugging commenced 3-26-83
 Plugging completed 3-26-83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 4590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	353'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

- Mud to 1980', Spot 50 sx. cement thru drill pipe.
- Mud to 1020', Spot 40 sx. cement thru drill pipe.
- Mud to 360', Spot 40 sx. cement thru drill pipe.
- Mud to 40', Plug, Spot 10 sx. cement thru drill pipe.
- Spot 15 sx. cement in rathole thru drill pipe.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita
 (Address) Ks. 672


SUBSCRIBED AND SWORN TO before me this 8th day of April, 1983



Viva McGee
 Notary Public.

Nov. 7, 1983 STATE CORPORATION COMMISSION

APR 12 1983
 4-12-83
 CONSERVATION DIVISION
 Wichita, Kansas



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Raymond Oil Co., Inc. Suite 900 One Main Place, Wichita, Kansas 67202
CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Bondurant Well No. #1
Sec. 25 T. 16S R. 26W Spot SE NW SW
County Ness State Kansas Elevation 2617' GL

Casing Record:

Surface: 8 5/8" @ 353' with 200' SX. 2%gel
3%cc

Production: @ with SX.

Type Well: D & A Total Depth 4590'

Drilling Commenced 3-18-83 Drilling Completed 3-26-83

Formation	From	To	Tops	
Cellar	0	7	Mississippi	4573
Sand, Shale	7	2040		
Shale	2040	2144		
Sand, Shale	2144	2620		
Shale, Lime	2620	3730		
Lime, Shale	3730	3947		
Shale, Lime	3947	4342		
Lime, Shale	4342	4465		
Lime	4465	4480		
Chert	4480	4590		

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1983

CONSERVATION DIVISION
Wichita, Kansas