

LEASE NAME Dirreen

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4950 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 20 TWP. 17S RGE. 14W (E) or (W)

COUNTY Barton

LEASE OPERATOR Russell Oil, Inc.

ADDRESS 3535 N.W. 58th St, Suite 1060, Okla City, OK. 73112

PHONE# (405) 947-9900 OPERATORS LICENSE NO. 3293

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-11-01

Plugging Completed 5-15-01

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3406'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	875'	None
				5-1/2"	3398	2410'

MAY 23 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 2960' and 5 sks. cement. Shot pipe @2410', pulled up to 1560', pumped 130 sks. cement w/200# hulls, pulled up to 870', pumped 110 sks. cement and circulated to surface,, 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of May, 2001

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



OR