

15-077-00104-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1965
03-15-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Zuercher Well No. # 1

Location C NE SW Sec. 18 Twp. 32 Rge. 7 (E) (W) W

County Harper Total Depth 4855'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractors: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:00AM Day 13th Month March Year 1965

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cemented with 175 sacks. 4660' of 5 1/2" long
string, cemented with 150 sacks. Top perforation 4420'. Bottom of the
hole was sanded to 4365', and cemented with 5 sacks. 3300' of 5 1/2" long
string was recovered from the hole. Fluid in the hole was bailed down
to 240'. Bridge plug set on fluid at 240', and 10' of rock bridge, and
cemented with 25 sacks. Hole was filled with mud to 40', and 10' of
rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 3/15/65
INV. NO. 809-W
INV. NO.

Signed: Archie Elving
Well Plugging Supervisor