

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 077 - 20; 357 - 00 - 00 (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Larsen Well No. 1

Location Appr. NWNW NE Sec. 16 Twp. 32S Rge. 7 (E) (W) X

County Harper Total Depth 4762

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 11:15 Am. Day 21 Month 7 Year 1980

The above well was plugged as follows:

246' 8 5/8" casing W/250 sax cement. 4 1/2" casing set at 4665' W/275 sax cement. Plug back to 4523' - Top perforation at 3844' - Push plug to 3800' Sand back to 3755' - Top sand W/4 sax mixed cement W/dump bailer. Pull 3525' casing - Bridge at 300' & 4 1/2 yards grout in 8 5/8" casing to top of casing. By Harper Ready Mix.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 7-23-80  
INV. NO. 2673-W

Signed: [Signature]  
Well Plugging SUPERVISOR  
STATE CORPORATION COMMISSION  
**RECEIVED**  
07-23-1980  
**JUL 23 1980**  
CONSERVATION DIVISION  
Wichita, Kansas