

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
09-12-1977
SEP 12 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -077 - 20401-00-00 (of this well)

Operator's Full Name Texas Oil & Gas. Corp.
Complete Address 200 W. Douglas, Suite 300, Wichita, Kans. - 67202
Lease Name Schiefelbine Well No. 1
Location C. 5/2 SW. Sec. 15 Twp 32 Rge. 7 (E) (W) X
County Harper Total Depth 4399
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____

Plugging Contractor Clark Corporation
Address 107 W. Fowler, Medicine, Lodge # 67104 License No. 583
Operation Completed: Hour 11:15 AM Day 9 Month Sept. Year 1977

The above well was plugged as follows:

282' - 8 5/8" surface pipe Cement Circ - 4 1/2" casing set @ 4384' cemented
w/ 125 sq Cement - open hole - sand back to 4375' mix
& dump 4 sq Cement w/ dump trailer - Set bridge
@ 282' - 4 yard Ready mix Cement to top of surface pipe
Recovered 3910' - 4 1/2" casing
Ready mix Cement, Harper Kans.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Owen
Well Plugging Supervisor

INVOICED

DATE 9-12-77
INV. NO. 5823-W