

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1972
6-5-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Company

Complete Address 435 Page-Court - 220 W. Douglas Wichita, Kansas

Lease Name Peters Well No. 1

Location C SW NW NE Sec. 21 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4570'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Oulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 10:30 A Day 1 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4570' 8 5/8 csg set at 255' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

5 1/2 csg set at 4560' cwc 150 sk cmt.

Filled 5 1/2 csg W/sd (4535-4570) dumped 5 sk cmt W/dump bailer. (4500-4535)

Pumped down 8 5/8 csg with 200 lbs hulls, 20 sk gel & water, 100 lbs hulls, 70 sk cmt.

12 sk gel & water, released 8 5/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. A. [Signature]
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5818-W