

CP3

✓

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22, 349-60005

NW SW, Sec. 19, T 16 S, R 26 W1/4

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name Horchem Well # 1

Operator: Sabre Exploration Inc.
Name & Address 105 S. Broadway
Suite 730
Wichita KS. 67202

County Ness

Well Total Depth 4560 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Drilling License Number 5149

Address P.O. Box 947 Pratt KS. 67124

Company to plug at: Hour: 3:00 pm Day: 6 Month: 2 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO _____

(company name) Wheatstate Drilling (phone) _____

were: 50/50 Pozmix 4% gel 3% cc

1st plug 2100' w/70sx, 2nd plug 1260' w/70sx

3rd plug 420' w/40sx, 4th 40'-0' 1/2sx hulls

+ wiper plug w/10sx circ 10sx in Rathole

200sx

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:00 pm Day: 6 Month: 2 Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered
cementing done Allied cement

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1983
2-10-83
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Bob Tarbutton gave orders

surface pipe cemented with 250sx common

Anhydrite 2087-2120 Dakota 1600

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 2-10-83

INV. NO. 2560-w

Signed Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82



Oilfield Services, Inc.

15135-22349-0000

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS: WELL LOG

HORCHEM # 1
 C NW SW Sec. 19-16S-26W
 Ness County, Kansas
 Commenced : 1-27-83
 Completed : 2-06-83
 Operator : Sabre Exploration, Inc.

RECEIVED
 STATE CORPORATION COMMISSION

FEB 11 1983

CONSERVATION DIVISION
 Wichita, Kansas


DEPTH		FORMATION	REMARKS
From	To		
-0-	384	Surface Clay	Spud 1-27-83. Drilled to 384', set 9 joints, 362' of 8 5/8", 24#, new surface casing set at 371'. Cemented with 250 sxs common, 2% gel, 3 % CC. Cement did circulate. Plug down at 12:45 A.M. 1-28-83. Cement job by Allied.
384	2115	Shale	
2115	2795	Lime & Shale	
2795	3270	Lime	
3270	3690	Shale & Lime	
3690	4098	Shale & Lime	
4098	4174	Lime & Shale	
4174	4390	Lime & Shale	
4390	4480	Lime & Shale	
4480	4560	Lime & Shale R.T.D.	

STATE OF KANSAS)
) SC
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

J. H. Belding
 J. H. BELDING VICE-PRESIDENT



Darlene Butts
 Darlene Butts
 Notary Public

My Commission Expires:
April 23, 1983