

KANSAS

STATE CORPORATION COMMISSION

15135.20581-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling and Petroleum Resources
Complete Address Box 18407 Wichita, Kansas
Lease Name McBee "A" Well No. 1
Location NW SE NE Sec. 19 Twp. 16 Rge. (E) (W) 26
County Ness Total Depth 4568'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Strata Drilling (Rotary)
Address Wichita, Kansas License No.
Operation Completed: Hour 11:30 A Day 12 Month 3 Year 1972

The above well was plugged as follows:

RTD 4568' 8 5/8 csg set at 338' cwc 175 sk. Cmt. Mat. 100 sk Halco-Light.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3-17-72
INV. NO. 5368-W