

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 20527-0000 CONSERVATION DIVISION
Wichita, Kansas

DEC - 4 1978
12-4-78

Operator's Full Name Thunderbird Drilling Co., Inc.
Complete Address Box 97, Ellinwood, Kansas 67526
Lease Name Horchem "G" Well No. 1
Location NW NW SW Sec. 19 Twp. 16 Rge. (E) (W) 26
County Ness Total Depth 4553'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 3:45 P Day 29 Month 11 Year 1978
The above well was plugged as follows:
Total Depth 4553' 8 5/8 csg set 330' cwc 200 sk.
5 1/2 csg set 4544' cw 150 sk cem.
5 1/2 csg PBTD 4494' PFS (4456'-4316')
Filled 5 1/2 csg W/sd (4494'-4300') dumped 4 sk cem W/dump bailer. (4300'-4270')
Cutoff & Recovered 899' of 5 1/2 csg.
Hallib. mixed & pumped down 8 5/8 csg with 25 sk gel & Water W/100 lbs hulls -
released cementing plug & capped with 120 sk 50-50 poz 6% & shutin. FPP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-6-78
8677.0

Signed: Red Messing
Well Plugging Supervisor