

KANSAS

*M*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-077-30174-00-00

Operator's Full Name ALADDIN PETROLEUM CORP.

Complete Address 809 PET. BLDG. WICHITA, KS.

Lease Name MAUD TRUSTEE Well No. I

Location NW/NW/NW Sec. 26 Twp. 33 Rge. 5 (E) (W) L

County HARPER Total Depth 4900

Abandoned Oil Well L Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor FORBES CASING PULLING Co.

Address Box 221 GREAT BEND, KANS License No. 49

Operation Completed: Hour 6 P.M. Day 16 Month 1 Year 1970

The above well was plugged as follows:

243 FT OF 8 5/8 SURFACE PIPE 4877 FT OF 4 1/2 LONG STRING  
TOP PERF. 4850 FT SAND TO 4840 FT 3 SACKS CEMENT  
WITH BAILER. 4221 OF 4 1/2 LONG STRING PULLED. BAILED  
HOLE TO 235 FT SET PLUG 10 FT ROCK BRIDGE FILL WITH  
3 YDS REDIMIX CEMENT + MUD MUD TO 30 FT + FILL  
WITH REDIMIX <sup>CEMENT</sup> TO TOP OF SURFACE

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: Russell B. Berstein  
Well Plugging Supervisor

INVOICED

JAN 19 1970

CONSERVATION DIVISION  
Wichita, Kansas

DATE 1/19/70

INV. NO. 1275-w

01-19-1970