

15-055-20085-0250

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED  
JUL 5 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Skelly Oil Company  
Complete Address 1860 Lincoln St., Denver, Colorado 80203  
Lease Name Finnup "A" Well No. 1  
Location C SWNW Sec. 28 Twp. 21 Rge. 33 ~~(E)~~ (W)  
County Finney Total Depth 4800'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Southwest Casing Pulling  
Address Box 364, Great Bend, Kansas License No. 399  
Operation Completed: Hour 2:00PM Day 30 Month 6 Year 1972

The above well was plugged as follows:

10 3/4" to 814' circulated w/ cement. 5 1/2" to 4686' cemented.  
Top perforations 4572' plug bottom w/ sand & 5 sacks cement.  
Top of cement 4500' Mud 4500' to 800'  
Spotted 60 sacks cement 800' to 700' Mud 800' to 40'  
Plug. & 15 sacks cement 40' to 0'. Halliburton Pump Truck  
Pulled 2740' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/5/72  
INV. NO. 5989-W