

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1967
4-21-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Kerrm Drilling Co. Inc.

Complete Address: 337 Union Center Wichita, Kansas

Lease Name Furman Well No. 1

Location C SE NE Sec. 26 Twp. 16 Rge. 26 (E) (W) X

County Ness Total Depth 4630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Hellar Drilling Co.

Address: Wichita, Kansas License No.

Operation Completed: Hour 4:15 A Day 18 Month 4 Year 1967

The Above well was plugged as follows:

RTD 4630' 8 5/8 csg set at 275' cwc 250 sc.
Gunned pits, circulated heavy mud, set cementing plug at 1000' and displaced 30 sc cem.
thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messing
Well Plugging Supervisor

DATE 4/21/67
INV. NO. 5086-4