

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECORDED
STATE CORPORATION COMMISSION
FEB 18 1963
2-18-63
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Petroleum Inc

Complete Address: Box 433 Great Bend, Kansas

Lease Name Peters Well No. 1

Location CNE NE Sec. 26 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4600

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Garvey Drg Co

Address: Great Bend, Kans License No.

Operation Completed: Hour 7:30AM Day 16 Month 2 Year 63

The Above well was plugged as follows:

8 5/8" 258' circulated with cement.

Circulated hole with heavy mud, set plug at 740', displaced 20 sax cement
through drill pipe, heavy mud to 240', set plug and displaced 20 sax cement
through drill pipe, heavy mud to 40', set plug, 1/2 sack hulls and filled
to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leon Letty
Well Plugging Supervisor

INVOICED

DATE 2/18/63
INV. NO. 6594-W