

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-22066-6200

LEASE NAME Stutz

WELL NUMBER 1

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 25 TWP. 16 SRGE. 26 (X) or (W)

COUNTY Ness

Date Well Completed 8/81

Plugging Commenced 8-10-89

Plugging Completed 8-11-89 11 A.M.

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box # 97, Ellinwood, Kansas 67526

PHONE # 3160 564-2577 OPERATORS LICENSE NO. 5131

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-10-89 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? log filed w/application

Producing Formation Miss. Depth to Top 4520 Bottom 4529 T.D. 4529

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled |
|-----------|---------|------|----|-------|--------|--------|
| | | | | 8 5/8 | 356 | 0 |
| | | | | 4 1/2 | 4522 | 1397 |
| | | | | | | |
| | | | | | | |

RECEIVED
 8-15-89
 AUG 15 1989
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
tubing & rods sanded in. cut off both at 3755. dumped 4 sacks cement. shot off 4 1/2 casing @ 1397. Allied Cementing plugged with 400# hulls, 70 sacks cement, 10 sacks gel, 100 # hulls, and 150 sacks cement. S.I.P. 100 # (cement 60/40 with 6 % gel)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Thunderbird & Cheyenne License No. 5131 & 06454

Address P. O. Box # 97, Ellinwood, Kansas 67526

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

Maynard Weber (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Maynard Weber

(Address) P. O. Box # 97, Ellinwood, Ks. 67526

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 89



Trevlyn Detmer
 Notary Public
 My Commission Expires: Jan. 21, 1990