

STATE OF KANSAS  
ATE CORPORATION COMMISSION  
3 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-02-3-117

RECEIVED

API NUMBER 15-135-22,655-00-00

LEASE NAME Horchem "F"

WELL NUMBER 1

2310 Ft. from S Section Line

4780 Ft. from E Section Line

SEC. 28 TWP. 16 RGE. 26W (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-09-01

Plugging Completed 10-10-01

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th St. Newton, Kansas 67114-8827

PHONE#(316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on \_\_\_\_\_ (date)

Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4588

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 387'   | None.      |
|           |         |      |    | 4-1/2" | 4584'  | 700'       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4525' and 4 sks. cement. Shot pipe @1200', pumped 80 sks. cement and displaced to 800', shot pipe @700', pulled up to 410', pumped 50 sks. cement, pulled up to 40' and pumped 20 sks. cement to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of October, 2001

My Commission Expires: \_\_\_\_\_

