

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas, 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ness SEC. 28 TWP. 16s RGE. 26w E/W  
Location as in quarters or footage from lines:  
NE NW SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Rains & Williamson Oil Co., Inc.  
Lease Name Horchem #1 Well No. \_\_\_\_\_  
Office Address 220 W. Douglas, 435 Page Court Bldg, Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole): 67202  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 6/23/83  
Plugging completed 6/28/83  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4590'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	251'	none
				5 1/2"	4576'	837.20'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4525' & ran 5 sacks cement. Shot  
pipe at 1510', 1000', & 835'. Pulled total of 20 joints. Squeezed hole with  
3 hulls, 10 gel, 70 cement, 15 gel, 1 hulls. Released plug & displaced with 130  
sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1983



[Signature]  
STATE CORPORATION COMMISSION Notary Public.

My Commission expires: \_\_\_\_\_

JUL 05 1983  
7-5-83  
CONSERVATION DIVISION  
Wichita, Kansas

15-135-20467-0000

ROTARY DRILLING LOG

Operator: Rains & Williamson  
Oil Co., Inc.  
HORCHEM #1  
NE NW SW Section 28-16S-26W  
Ness County, Kansas

Contractor: Rains & Williamson  
Oil Co., Inc.  
Commenced: 8-10-71  
Completed: 8-20-71

Casing: 8-5/8"/251'/180 sacks  
5-1/2"/4576'/125 sacks

Formations


Clay	40'
Sand	70'
Sand and Shale	100'
Shale	1565'
Sand	1800'
Shale	2073'
Anhydrite	2120'
Shale and Lime	2375'
Lime and Shale	3230'
Shale and Lime	3560'
Lime and Shale	3642'
Lime	4585'
Mississippi	4590'

We certify the above log is true and correct, to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

  
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 27 day of August, 1971.

  
Jeanine Durand Notary Public

My Commission Expires: 3-31-74



RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1983

CONSERVATION DIVISION  
Wichita, Kansas