



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 1972
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bear of Skelly has this

date requested permission to plug the following described well:

Mr. Bear guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name: Finnup "A" Well No. 1

Location: C SW NW Sec. 28 Twp. 21 Rge. 33 ^{XX}(E)(W)

County: Finney Total Depth 4800' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bear was instructed to plug the well as follows:

10 3/4" to 814' circulated w/ cement. 5 1/2" to 4686' cemented.

Top perforations 4572' Plug, bottom w/ sand & 5 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spot 60 sacks cement 800' to 700' Mud 700' to 40'

Plug, Hulls ^{cc} 15 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Fries
Conservation Division Agent