

State of Kansas



15135-20623-0600

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1967
4-21-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of Hellar Drlg. co. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Kern Drilling Co. Inc.

Complete Address: 337 Union Center Wichita, Kansas

Lease Name: Furman Well No. 1

Location: C SE NE Sec. 26 Twp. 16 Rge. 26 (E)(W) X

County Ness Total Depth 4630' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

Gun pits, circulate heavy muf, set cementing plug at 1000' and displace
20 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Geo. F. Massey
Conservation Division Agent