



15-007-61504-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

SEP 28 1964
09-28-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Richard McCullum of Sierra Petroleum Co., Inc has this date requested permission to plug the following described well:

Mr. McCullum guarantees payment of the plugging fee.

Operator's full Name: E. H. Wood & Colorado Oil & Gas Corp.

Complete Address: 403 Kaufman Bldg., Wichita, Kansas

Lease Name: Zvolanek Well No. # 1

Location: C NW NE Sec. 11 Twp. 32 Rge. 10 (E) (W) W

County Barber Total Depth 4410 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McCullum was instructed to plug the well as follows:

208' of 8 5/8" surface pipe, cement circulated with 165 sacks.
Fill hole with drilling mud to 200', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving