



CP 2

15:135:70496-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas
10-18-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hunt of Rains & Williamson Oil has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Co.

Complete Address: 220 W. Douglas Wichita, Ks.

Lease Name: Anspaugh "B" Well No. 1

Location: NW SE Sec. 29 Twp. 17 Rge. (E)(W) 23

County: Ness Total Depth 4448' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Hunt was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 700' and displace
70 sk cmt thru drill pipe. Heavy mud to 190' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Lucas J. Massey
Conservation Division Agent