



CP2

15-135-20266-0000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Berens of DNB Drlg. has this date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.

Operator's full Name: DNB Drlg., & Comet Petr. Co.

Complete Address: 737 1st Nat'l Bank Bldg., Wichita, Ks.

Lease Name: Lynch "A" Well No. 1

Location: C SW NW Sec. 29 Twp. 17 Rge. (E)(W) 23

County: Ness Total Depth 4500' Oil Well

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Berens was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with

2 sk cmt.

RECEIVED  
 STATE CORPORATION COMMISSION

7-24-69  
 JUL 24 1969

Very truly yours,

CONSERVATION DIVISION  
 Wichita, Kansas

Len F. Munday  
 Conservation Division Agent