



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Secretary

STATE CORPORATION COMMISSION

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

9-26-82

OCT 01 1982

10-1-82

CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM

(To be filed by Plugging Agent)

15-135-21,293-0000

Dear Sir:

Mr. Herbert French of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Pickrell Drilling Co.

Complete Address: Litwin Bldg Suite 205, Wichita, Kans 67202

Lease Name: Dunbar L. M. Well No. 5

Location: C-NW-SW Sec. 35 Twp. 16 Rge. 26 (E) (W)

County: Ness Total Depth: 4552'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. French was instructed to plug the well as follows:

8 1/8" - 572' surface casing cement circulated with common cement.  
260 sbx 3% gel + 2% cc. 1st plug @ 1800' w/ 60 sbx cement. 2nd plug  
@ 630' w/ 40 sbx cement. 3rd plug @ 40' to 0' on solid bridge w/ 10 sbx  
cement. Circulated 10 sbx of cement, in 4 at hole. The cement used  
was common w/ 3% gel + 2% cc. The plugging was completed  
by Allied Cementing.

Very truly yours,

Paul A. Luthie  
Conservation Division Agent