



CP2

15-135-70586-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-28-72
MAR 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Biggs of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. Biggs guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co. & Petro-Chem

Complete Address: 705 Fourth Nat'l Bank Bldg., Wichita, Ks.

Lease Name: Dunler L-M Unit Well No. 4

Location: A/C SW SE Sec. 34 Twp. 16 Rge. (E)(W) 26

County: Ness Total Depth 4545' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Biggs was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Messerly
Conservation Division Agent