

15-135-20496-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas
10-18-71

Operator's Full Name Mull Drilling Company

Complete Address 220 W. Douglas Wichita, Kansas

Lease Name Anspaugh "B" Well No. 1

Location NW SE Sec. 29 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4448'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil.

Address Wichita, Kansas License No.

Operation Completed: Hour 5:15 P Day 17 Month 10 Year 1971

The above well was plugged as follows:

RTD 4448' 8 5/8 csg set at 203' cwc: Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 190' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-18-71

INV. NO. 4490-47

Signed: [Signature]
Well Plugging Supervisor