

15.135.20266.0000

Form CP-3
Rev. 6-4-68

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name DNB Drlg. & Comet Petroleum, Inc.

Complete Address 737 1st Nat'l Bank Bldg., Wichita, Kansas

Lease Name Lynch "A" Well No. 1

Location C SW NW Sec. 29 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools (DNB)

Address Wichita, Kansas License No.

Operation Completed: Hour 9A Day 22 Month 7 Year 1969

The above well was plugged as follows:

RTD 4500' 8 5/8 csg set at 286' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt.
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar. Plugged rat hole with 2 sk cmt.

RECEIVED
STATE CORPORATION COMMISSION
7-24-69
JUL 24 1969

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 7/24/69
INV. NO. 155-W