

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21446 0001 (of this well)

Operator's Full Name Montgomery Drlg. Program

Complete Address 235 Montgomery St., Suite 1114, San Francisco, Cal.

Lease Name Anspaugh Well No. 1

Location C NE NW Sec. 28 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4470'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11 A Day 7 Month 3 Year 1979

The above well was plugged as follows:

Total Depth 4470' 8 5/8 csg set 287' cwc 190 sk.

4 1/2 csg set 4460' cw 100 sx cem.

4 1/2 csg PBT 4460' PFS (4413' - 4418')

Set 4 1/2 wood plug at 4300' - poured 10' sd - dumped 3 sk cem W/dump bailer. (4300' - 4260')

Cutoff & recovered 3710' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water - followed with 70 sk 50-50 poz 2% - displaced with 8 sk gel & water - released cementing plug & capped with 100 lbs hulls & 70 sk 50-50 poz 2% & shutin. FPP 400 lbs

I hereby certify that the above well was plugged as herein stated

INVOICED

DATE 3-13-79

INV. NO. 9255-6

Signed: Leon M. [Signature]
Well Plugging Supervisor

STATE CORPORATION COMMISSION
RECEIVED
MAR 13 1979
3-13-79
CONSERVATION DIVISION
Wichita, Kansas