

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 21,408-000 (is well)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1978  
4-24-78  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Strata Drilling Co.

Complete Address Box 355, Great Bend, Kansas

Lease Name Lehner Well No. 2

Location C SW SW Sec. 27 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4415'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 5:30 P Day 22 Month 4 Year 1978

The above well was plugged as follows:

RTD 4415# 8 5/8 csg set 292' cwc 180 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 650' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-26-78

INV. NO. 7173-W

Signed: Leo Massey  
Well Plugging Supervisor