

2

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR - 5 1979
3-5-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21559 0000 (of this well)

Operator's Full Name Pickrell Drlg. Co.

Complete Address 203 Litwin Bldg., Wichita, Ks.

Lease Name Horchem "M" Well No. 3

Location NE SW NE Sec. 32 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4595'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 3:15 P Day 1 Month 3 Year 1979

The above well was plugged as follows:

Total Depth 4595' 8 5/8 csg set 223' cwc 150 sk.

4 1/2 csg set 4585' cw 150 sk cem.

Filled 4 1/2 csg W/sd (4595'-4550') dumped 3 sk cem W/dump bailer. (4550'-4520')

Cutoff & recovered A/2500' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water -followed with 70 sk 50-50 poz 2% -displaced with 8 sk gel & water & released cementing plug & capped with 70 sk 50-50 poz 2% & shutin. FPP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-7-79
INV. NO. 9221-W