

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1978
1-27-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,413 - 00001 (of this well)

Operator's Full Name Chief Drlg. Co., Inc.

Complete Address 905 Century Plaza, Wichita, Kansas

Lease Name Hopkins Well No. 1

Location C SE NE Sec. 35 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4580'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Warrior Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4 P Day 25 Month 1 Year 1978

The above well was plugged as follows:
RTD 4580' 8 5/8 csg set 275' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 900' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-30-78
INV. NO. 6660-W

Signed: *Geo Massey*
Well Plugging Supervisor