

KANSAS

Form CP-3
Rev. 6-4-68

15135-76554-0008

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 06 1976
10-6-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company

Complete Address 205 Litwin Bldg., Wichita, Kansas 67202

Lease Name Dumler "LM" Unit Well No. 3

Location C NE SE Sec. 34 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4540'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc., Wellington, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 3 P Day 4 Month 10 Year 1976

The above well was plugged as follows:

Total Depth 4540' 8 5/8 csg set 270' cwc 160 sx.

5 1/2 csg set 4520' cw 150 sx cem.

Filled 5 1/2 csg W/sd (4540'-4500') dumped 5 sx cem W/dump bailer. (4500'-4465')

Cutoff & recovered 1511' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls -70 sk 60-40 poz cem. -displaced with 10 sk gel & water -released plug &

capped with 50 sk 60-40 poz cem. & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Masney
Well Plugging Supervisor

INVOICED

DATE 10-6-76

INV. NO. 3952-W